GENERAL NOTES / CODE NOTES

1. CARPET WILL BE OWNER PROVIDED & CONTRACTOR INSTALLED. GC WILL BE RESPONSIBLE FOR PROVIDING TAKE-OFFS TO THE OWNER AND COORDINATING DELIVERY OF MATERIALS FROM THE OWNERS PREFERRED SUPPLIER.
2. SEE LARGE SCALE ELEVATIONS FOR MIRROR LOCATIONS & TILE PATTERN AT WET WALL LOCATIONS.
3. BASE IN TOILET ROOMS ON WALLS WITH VWC-3 SHOULD MATCH CT-1
4. SS-1 COUNTERS SHOULD BE DOUBLE EASED EDGE
5. DOOR FRAMES ARE TO BE SEMI-GLOSS FINISH.
6. APPLIANCES WILL BE OWNER PROVIDED & CONTRACTOR INSTALLED.

FINISH SCHEDULE

ROOM NUMBER AREA DESIGNATION	ROOM OR AREA NAME	FLOOR	BASE	WALL					CABINETS						MISCELLANEOUS									REMARKS
				NORTH	SOUTH	EAST	WEST		COUNTER / BACKSPLASH	BASE / TALL CABINETS	UPPER CABINETS				DOOR FRAMES	TACKBOARDS	MARKERBOARDS	TOILET PARTITIONS	WINDOW TREATMENT	MIRRORS				
100	VESTIBULE	EM-1	RB-1	VWC-1	VWC-1	VWC-1	VWC-1		-	-	-				P-2	-	-	-	-	-				-
101	TOUCH DOWN	C-1 & C-2	RB-1	VWC-1	VWC-1	VWC-1	VWC-1		-	-	-				P-2	-	-	-	RS-1	-				PAINT EXISTING RADIATORS P-4
102	LUGGAGE STORAGE	C-1	RB-1	VWC-1	VWC-1	VWC-1	VWC-1		-	-	-				P-2	-	-	-	-	-				-
103	LAN	VCT-1	RB-1	P-1	P-1	P-1	P-1		-	-	-				P-2	-	-	-	-	-				-
104	COMPUTER CLOSET	C-1	RB-1	P-1	P-1	P-1	P-1		-	-	-				P-2	-	-	-	-	-				SHELF & POLE
105	RECEPTION	C-1	RB-1	VWC-1	-	VWC-2	VWC-1		-	-	-				P-2	-	-	-	RS-1	-				WOOD TOP CAP ON 1/2 HEIGHT WALL
106	MECHANICAL	VCT-1	RB-1	P-1	P-1	P-1	P-1		-	-	-				P-2	-	-	-	-	-				-
107	WORK ROOM/ STORAGE	VCT-1	RB-1	P-1	P-1	P-1	P-1		PL-2	PL-1	PL-1				P-2	-	-	-	RS-2	-				SEE A10.1 FOR ELEVATION OF MILLWORK
108	CORRIDOR	C-1	RB-1	VWC-1	VWC-1	VWC-1	VWC-1		-	-	-				P-2	-	-	-	RS-1	-				-
109	VIDEO CONFERENCE	C-1 & C-2	RB-1	VWC-1	VWC-1	VWC-1	VWC-1		-	-	-				P-2	-	-	-	RS-1	-				TECHNOLOGY N.I.C.
110	TRAINING ROOM #3	C-1 & C-2	RB-1	VWC-1	VWC-1	VWC-1	VWC-1		-	-	-				P-2	-	-	-	RS-1	-				TECHNOLOGY N.I.C.
111	TRAINING ROOM #1	C-1 & C-2	RB-1	VWC-1	VWC-1	VWC-1	VWC-1		-	PL-1	-				P-2	-	-	-	RS-1	-				TECHNOLOGY N.I.C.
112	TRAINING ROOM #2	C-1 & C-2	RB-1	VWC-1	VWC-1	VWC-1	VWC-1		-	-	-				P-2	-	-	-	RS-1	-				TECHNOLOGY N.I.C.
113	CORRIDOR	C-1	RB-1	P-3	VWC-1	VWC-1	VWC-1		SS-1	PL-1	-				P-2	-	-	-	-	-				SEE A10.1 FOR SERVERY COUNTER ELEVATIONS W/ GT-1 LOCATION
114	LUNCH ROOM	SF-1	RB-1	VWC-1	VWC-1	VWC-1	VWC-1		SS-1	PL-3	-				P-2	-	-	-	RS-2	-				SEE A10.2 FOR MILLWORK ELEVATIONS
115	KITCHEN	VCT-1	RB-1	VWC-1	VWC-1	VWC-1	VWC-1		SS-1	PL-1	PL-1				P-2	-	-	-	-	-				PAINT WINDOW FRAME P-2
116	JAN. CLOSET	SC	RB-1	P-1	P-1	P-1	P-1		-	-	-				P-2	-	-	-	-	-				-
117	WOMEN	CT-1	CTB-1&CWT	VWC-3	VWC-3	CWT-1&2	CWT-1&2		SS-1	-	-				P-2	-	-	Y	-	Y				SEE LARGE SCALE PLANS FOR CWT PATTERN
118	CORRIDOR	C-1	RB-1	VWC-1	VWC-1	VWC-1 & GT-1	VWC-1		SS-1	PL-1	PL-1				P-2	-	-	-	-	-				SEE A10.1 FOR MILLWORK ELEVATIONS & WATER FOUNTAIN ELEV
119	MEN	CT-1	CTB-1&CWT	CWT-1&2	CWT-1&2	VWC-3	VWC-3		SS-1	-	-				P-2	-	-	Y	-	Y				SEE LARGE SCALE PLANS FOR CWT PATTERN

ABBREVIATIONS

AWP - ACOUSTICAL WALL PANEL
BB - BULLETIN BOARD
BC - BASE CABINET
C - CARPET (TILE AND/OR BROADLOOM)
CBD - CHALK BOARD
CT - CERAMIC FLOOR TILE
CTB - CERAMIC TILE BASE
CTR - COUNTER
CWT - CERAMIC WALL TILE
DC - DISPLAY CASE
EM - ENTRY MAT
EP - EPOXY PAINT
ER - EPOXY RESIN FLOORING
ET - EPOXY TERRAZZO
GT - GROUT
HB - HORIZONTAL BLINDS
L - LINOLEUM
LS - LINOLEUM SHEET FLOORING
LT - LINOLEUM TILE
MBD - MARKER BOARD
MCIC - MULTI-COLORED INTERIOR COATING
MP - METAL PANEL
MS - MOTORISED SHADE
P - PAINT
PJS - PROJECTION SCREEN
PL - PLASTIC LAMINATE
RB - RESILIENT BASE
RF - RESILIENT FLOORING
RF - RUBBER FLOORING
RT - RESILIENT TILE
RT - RUBBER TILE
SDT - STATIC DISAPATIVE TILE
SS - SOLID SURFACE
SV - SHEET VINYL FLOORING
TB - TACK BOARD
TBD - TACK BOARD
TF - TERRAZZO FLOORING
TS - TACK STRIP
UC - UPPER (WALL) CABINET
VB - VERTICAL BLINDS
VB - VINYL BASE
VCT - VINYL COMPOSITION TILE
VF - VINYL FLOORING
VT - VINYL TILE
VWC - VINYL WALL COVERING
WB - WALL BASE
WC - WALK-OFF CARPET
WC - WALL COVERING
WD - WOOD
WM - WALK-OFF MAT
WO - WALK-OFF CARPET/MAT
WP - WALL PADDING/PROTECTION
WS - WINDOW SHADE

FINISH LEGEND

CARPET **owner provided & Contractor Installed

C-1: INTERFACE FLOR 18X18 TILE
STYLE: 1231302500, AQUA COLOURS 21Z * 50CM
COLOR: 8742 PLUMAGE

C-2: INTERFACE FLOR 18X18 TILE
STYLE: 1669002500, SOLID FOUNDATION 20Z * IC 50CM
COLOR: 5852 CANTON TEAL
CONTACT: HARRISON GANZ (203) 940-0236

ENTRY CARPET **owner provided & Contractor Installed

EM-1: INTERFACE CARPET
STYLE: ENTRY LEVEL 50CM X 50CM
COLOR: 7187 BLACK

RUBBER BASE

RB-1: ROPPE 4" COVE BASE
118 PEACOCK

SHEET FLOORING

SF-1: MANNINGTON COMMERCIAL 12'
STYLE: REALITIES
COLOR: 5621 MAPLE GROVE MAPLE
**HEAT WELD AT SEAMS

VINYL COMPOSITION TILE

VCT-1: MANNINGTON COMMERCIAL 12"X12"
STYLE: SOLID POINT
COLOR: 337 TOASTED SESAME

CERAMIC TILE

CT-1: AMERICAN OLEAN 2"x2"
STYLE: SANDY RIDGE
COLOR: SY02 ALMOND

GROUT

G-1: MAPEI SANDED GROUT
COLOR: #48 ALMOND
LOCATION: FLOORS

G-2: MAPEI UNSANDED GROUT
COLOR: #48 ALMOND
LOCATION: WALLS

SEALED CONCRETE: SC

WALLCOVERING

VWC-1: LANARK WALLCOVERING (FIELD)
STYLE: MARQUESSA
COLOR: LIGHT BEIGE, L2-MQ-02
CONTACT: JOHN BURGER (860)424-2408

VWC-2: YORK CONTRACT (ACCENT WALL)
COLLECTION: STACY GARCIA
PATTERN: MISAKI SG1988
CONTACT: JOHN BURGER (860)424-2408

VWC-3: TOWER WALLCOVERING (TOILET ROOMS)
PATTERN:HIGHWIRE
COLOR: DYNAMO T2-HW-16
CONTACT: BRIAN WEIR (800)231-3223

PAINT

P-1: SHERWIN WILLIAMS
SW2833 ROYCROFT VELLUM
FINISH: EGGSHELL

P-2: SHERWIN WILLIAMS
SW6489 REALLY TEAL
FINISH: SEMI-GLOSS (DOOR FRAMES)

P-3: SHERWIN WILLIAMS
SW6489 REALLY TEAL
FINISH: EGGSHELL (ACCENT WALLS)

P-4: ZOLATONE WATER BASE
PRISM COLORS
#ZL-00582P

ROLLER SHADES

RS-1: MECHO SHADE, MANUAL ROLLER SHADE WITH CHAIN
THERMOVEIL, 3000 SERIES SATIN & DIAMOND
COLOR: #3013 SAND / 2% OPEN
LOCATION: TRAINING ROOMS

RS-2: MECHO SHADE, MANUAL ROLLER SHADE WITH CHAIN
EUROTWILL, 6000 SERIES TWIL WEAVE
COLOR: 6004 SAND 3% OPEN
LOCATION: LUNCH ROOM & WORKROOM

PLASTIC LAMINATE

PL-1: WILSONART
7909-60 FUSION MAPLE (USE DOLLKEN WOODTAPE # 3422)
LOCATION: CABINETS

PL-2: PIONITE (USE DOLLKEN WOODTAPE # XXXX)
MT340 ROCK AROUND THE CLOCK
LOCATION: COUNTER IN WORKROOM

PL-3: WILSONART (USE DOLLKEN WOODTAPE # 6108)
4796-60 BURNISHED CHESTNUT
LOCATION: LOWER CAB IN LUNCH ROOM

SOLID SURFACE

SS-1: CORIAN
COLOR: TUMBLED GLASS
LOCATION: COUNTERS

TOILET PARTITIONS

TP-1: PSISC, PHENOLIC
FORMICA, 7014-58 COLORADO SLATE

GLASS TILE

GT-1: CROSSVILLE GLASS TILES
1"X1" GLASS BLOX - GBO5
MOUNTED ON 12"X12" SHEETS

CERAMIC WALL TILE

CWT-1: AMERICAN OLEAN
UNGLAZED MOSAICS
1" X 1" PENNY ROUND MOSAIC
COLOR: A24 ALMOND

CWT-2: AMERICAN OLEAN
UNGLAZED MOSAICS
1" X 1" PENNY ROUND MOSAIC
COLOR: A08 PEACOCK BLUE

PROGRESS
NOT FOR CONSTRUCTION
October 16, 2009

Plotted on Recycled Paper

DATE: 10-16-09
DRAWN BY: XXX
SCALE: XXX
REVIEWED BY: XXX
PROJECT NO. 28141 XXX

REVISIONS

NO.	DATE	DESCRIPTION

FINISH SCHEDULE AND NOTES

PROJECT NUMBER 28141
ADDITIONS AND RENOVATIONS
CIGNA UNIVERSITY
1350 HALL BOULEVARD
BLOOMFIELD, CONNECTICUT

FRIAR ASSOCIATES INC.
281 Farmington Avenue
Farmington, CT. 06032

SHEET NO.
A12.2