

DEMOLITION NOTES:

WALLS:

ROOF:

GENERAL DEMOLITION NOTES:


- 1 REMOVE EXISTING DOOR AND FRAME, PATCH ALL WALL SURFACES TO MATCH EXISTING ADJACENT SURFACES.
- 2 REMOVE EXISTING DOOR, FRAME AND SIDELIGHT.
- 3 REMOVE EXISTING ALUMINUM WINDOWS AND ASSOCIATED HARDWARE, PATCH ALL WALL SURFACES AS REQUIRED FOR INSTALLATION OF PLYWOOD OPENING ENCLOSURES.
- 4 REMOVE EXISTING WALL CONSTRUCTION FOR NEW DOOR OPENING OR OTHER CHASE LOCATIONS. REMOVE EXISTING DRINKING FOUNTAIN, TYPICAL, CUTBACK WASTE HOT & COLD WATER UP TO NEAREST ACTIVE MAINS & CAP. REFER TO MECHANICAL DRAWINGS FOR ADDITIONAL INFORMATION. CELLINGS.
- 5 REMOVE VERTICAL BLINDS, CURTAIN TRACK AND MOUNTING HARDWARE.
- 6 REMOVE EXISTING SUSPENDED ACOUSTICAL TILE CEILING SYSTEM & ASSOCIATED FRAMING TO STRUCTURE ABOVE, TYPICAL THROUGHOUT.
- 7 REMOVE EXISTING WALL CONSTRUCTION COMPLETE TO FLOOR DECK AND/OR STRUCTURE ABOVE. AT EXISTING FLOOR PROVIDE SMOOTH LEVEL & CLEAN SURFACE FOR NEW FINISH FLOOR SURFACES.
- 8 REMOVE EXISTING CLOSET DOORS & ASSOCIATED HARDWARE WITHIN WORK AREA.
- 9 REMOVE EXISTING FIXED UPPER & LOWER CABINETS, COMPLETE TO STRUCTURE ABOVE. EXISTING CABINETS FRAMING A CONSTRUCTION TO VERIFY IN FIELD CONSTRUCTION.
- 10 REMOVE EXISTING CERAMIC TILE REPAIR ANY DAMAGE TO THE EXISTING FLOOR SLAB & REMOVE ADHESIVE, PROVIDE SMOOTH LEVEL AND CLEAN SURFACE FOR NEW FINISH FLOORING, PROVIDE CONCRETE SLAB.
- 11 REMOVE EXISTING VINYL FLOORING, REPAIR ANY DAMAGE TO THE EXISTING FLOOR SLAB & REMOVE ADHESIVE, PROVIDE SMOOTH LEVEL AND CLEAN SURFACE FOR NEW FINISH FLOORING.
- 12 REMOVE EXISTING METAL CLAD FASCIA & HTL SOFFIT ASSOCIATED FLASHING, TYPICAL.
- 13 REMOVE EXISTING METAL CLAD FASCIA & HTL SOFFIT WITHIN WORK AREA.
- 14 REMOVE EXISTING ROOF INSULATION, TYPICAL AT EXISTING ATTIC.
- 15 REMOVE ALL INTERIOR WALLS SHOWN DOTTED. EXERCISE CAUTION SO AS NOT TO DISTURB OR DAMAGE ADJACENT SURFACES SCHEDULED TO REMAIN.
- 16 DEMOLITION CONTRACTOR TO FIELD VERIFY LOCATION OF TELEPHONE, TELECOM, ELECTRICAL, MECHANICAL, PLUMBING & ELECTRICAL REINFORCED POLYURETHANE SHEETING FOR PROTECTION OF SCHEDULED EQUIPMENT TO REMAIN.
- 17 REMOVE ALL LAVATORIES, DRINKING FOUNTAINS, WITHIN WORK AREA SHOWN DOTTED. REMOVE AND CAP ALL PLUMBING LINES BEHIND FINISHED WALL AND FLOOR SURFACES, PATCH ADJACENT WALL FINISHES TO MATCH ADJACENT.
- 18 REMOVE ALL DOORS AND DOOR HARDWARE SHOWN DOTTED. DISPOSE OF DOORS & ASSOCIATED HARDWARE UNLESS REQUESTED BY OWNER.
- 19 REMOVE ALL TOILET PARTITIONS WITHIN WORK AREA.
- 20 REMOVE ALL TOILET ACCESSORIES WITHIN WORK AREA.
- 21 REPAIR ALL DAMAGED CEILING, ATTIC GYPSON BOARD SHEATHING IN 5/8" FIRE CODE BOARD, PROVIDE 2X FRAMING AS REQUIRED.
- 22 REMOVE EXISTING ROOF INSULATION IN EXISTING ATTIC, TYPICAL.

DEMOLITION PLAN

SCALE: 1/4"=1'-0"

PROGRESS

NOT FOR CONSTRUCTION
October 16, 2009



DEMOLITION PLAN

PROJECT NUMBER 28141
ADDITIONS AND RENOVATIONS
CIGNA UNIVERSITY
1350 HALL BOULEVARD
BLOOMFIELD, CONNECTICUT

REVISIONS		
NO.	DATE	DESCRIPTION

DATE: 10-16-09
DRAWN BY: XXX
SCALE: XXX
REVIEWED BY: XXX
PROJECT NO. 28141
XXX

FRIAR ASSOCIATES INC.
281 Farmington Avenue
Farmington, CT 06032

SHEET NO. D1.1

♻️ Printed on Recycled Paper